

AD-A156 376


NATIONAL PROGRAMS FOR INSPECTION OF NON-FEDERAL DAMS  
BAKER FLOODWATER RES. (U) CORPS OF ENGINEERS WALTHAM MA  
NEW ENGLAND DIV JUN 79

1/2

UNCLASSIFIED

FIG 13/13 NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 376

MERRIMACK RIVER BASIN  
WARREN, NEW HAMPSHIRE

**BAKER FLOODWATER RESERVOIR  
SITE 2**

**NH 00231**

NHWRB NO. 244.10

**PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM**



DTIC FILE COPY

**DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154**

**DISTRIBUTION STATEMENT A**  
Approved for public release  
Distribution Unlimited

JUNE 1979

85 06 14 016

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00231	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Baker Floodwater Reservoir Site 2 NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE June 1979
		13. NUMBER OF PAGES 76
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Warren, New Hampshire Gerry Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a 805 ft. long, 68 ft. high earthen embankment structure with three different fill zones. The visual inspection indicated that the dam is in good condition. The inspection revealed minor deterioration of concrete on the riser structure and at the end of the 4 ft. diameter outlet pipe. It is intermediate in size with a high hazard potential. There are no recommendations for the dam based on the inspection report,		

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:

OCT 2 1979

NEDED

Honorable Hugh J. Callen  
Governor of the State of New Hampshire  
State House  
Concord, New Hampshire 03301

Dear Governor Callen:

I am forwarding to you a copy of the Baker Floodwater Reservoir, Site-2 Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, New Hampshire Water Resources Board, Concord, New Hampshire 03301.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,

A handwritten signature in dark ink, appearing to read "Max B. Scheider".

MAX B. SCHEIDER  
Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

BAKER FLOODWATER RESERVOIR SITE 2

NH 00231

NHWRB 244.10

MERRIMACK RIVER BASIN  
WARREN, NEW HAMPSHIRE

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist.	Avail and/or Special
A/	23 CV

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



LETTER OF TRANSMITTAL  
FROM THE CORPS OF ENGINEERS TO THE STATE  
TO BE SUPPLIED BY THE CORPS OF ENGINEERS



NATIONAL DAM INSPECTION PROGRAM  
PHASE I - INSPECTION REPORT  
BRIEF ASSESSMENT

Identification No.: 00231

Name of Dam: Baker Floodwater Reservoir Site 2

Town: Warren

County and State: Grafton, New Hampshire

Stream: Berry Brook

Date of Inspection: May 17, 1979

Baker Floodwater Reservoir Site 2 is a 805 foot long, 68 foot high earthen embankment structure, with three different fill zones. Top width of the dam is 20 feet. The slope of upstream and downstream embankments is  $2\frac{1}{4}$  horizontal to 1 vertical. Appurtenant structures consist of a concrete riser principal spillway with a 4.0 foot diameter discharge pipe. The principal spillway has two stages, an orifice type low stage inlet and a covered top high stage inlet. The principal spillway discharges to an impact type stilling basin. A vegetative lined emergency spillway 95 feet wide is located on the left side of the dam. There is a 24 inch diameter gated pond drain pipe. The dam construction was completed in September of 1969. As built construction plans, design data and construction data were available, and were prepared by the Soil Conservation Service.


The visual inspection indicated that the dam is in good condition. The inspection revealed minor deterioration of concrete on the riser structure and at the end of the 4 foot diameter outlet pipe. Also noted during the inspection was minor seepage of clear water on the right abutment and a surface erosion gully at the juncture of the downstream slope and the left abutment.

Based on the intermediate size of the dam and its high hazard classification and in accordance with Corps of Engineers guidelines, the test flood inflow is the Probable Maximum Flood (PMF) equal to 14,100 cfs. The routed test flood outflow of 10,000 cfs overtops the dam by approximately 0.8 feet. With the water level at the top of dam, the spillways will pass 54 percent of the routed test flood outflow. As there is a high hazard to loss of life from large flows downstream of the dam, a review was made using  $\frac{1}{2}$  the PMF. The

analysis indicates that the  $\frac{1}{2}$  PMF inflow would be 7,050 cfs. The routed  $\frac{1}{2}$  PMF outflow would be 3,460 cfs. As the maximum capacity of the spillways is 6,706 cfs there will be a freeboard of 3.0 feet. The test flood inflow was routed with the water surface starting at the recreational pool level. Hydraulic design calculations indicate that the principal spillway was designed to retard flood flows up to a 100 year frequency. The crest of the dam was designed using a total watershed runoff of 10.84 inches.

There are no recommendations for this dam based on the Phase I Inspection Report. Remedial measures include the development of a downstream warning system, repair of the deteriorated concrete on the riser and at the end of the 4 foot diameter discharge pipe, and observation and recording of seepage at the right abutment.


The remedial measures are described in Section 7 and should be addressed within 2 years after receipt of this Phase I Inspection Report by the owner.





Gordon H. Slaney, Jr., P.E.  
Project Engineer

Howard, Needles, Tammen & Bergendoff  
Boston, Massachusetts


This Phase I Inspection Report on Baker Floodwater Reservoir Site 2 has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

  
JOSEPH W. FINEGAN, JR., MEMBER  
Water Control Branch  
Engineering Division

  
CARNEY M. TERZIAN, MEMBER  
Design Branch  
Engineering Division

  
JOSEPH A. MCELROY, CHAIRMAN  
Chief, NED Materials Testing Lab.  
Foundations & Materials Branch  
Engineering Division

APPROVAL RECOMMENDED:

  
JOE B. FRYAR  
Chief, Engineering Division

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

## REPORT

1. PROJECT INFORMATION	1-1
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-2
f. Operator	1-2
g. Purpose of Dam	1-3
h. Design and Construction History	1-3
i. Normal Operational Procedure	1-3
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	2-1
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-3
e. Downstream Channel	3-4
3.2 Evaluation	3-4
4. OPERATIONAL PROCEDURES	4-1
4.1 Procedures	4-1
4.2 Maintenance of Dam	4-1
4.3 Maintenance of Operation Facilities	4-1
4.4 Description of any Warning System in Effect	4-1
4.5 Evaluation	4-1
5. HYDRAULIC/HYDROLOGY	5-1
5.1 Evaluation of Features	5-1
a. General	5-1
b. Design Data	5-1
c. Experience Data	5-1
d. Visual Observation	5-1
e. Overtopping Potential	5-1
f. Dam Failure Analysis	5-2
6. STRUCTURAL STABILITY	6-1
6.1 Evaluation of Structural Stability	6-1
a. Visual Observation	6-1
b. Design and Construction Data	6-1
c. Operating Records	6-1
d. Post-Construction Changes	6-1
e. Seismic Stability	6-1

<u>Section</u>	<u>Page</u>
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	7-1
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
d. Need for Additional Investigation	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
7.4 Alternatives	7-2

#### APPENDIXES

APPENDIX A - INSPECTION CHECKLIST

APPENDIX B - ENGINEERING DATA

APPENDIX C - PHOTOGRAPHS


APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL  
INVENTORY OF DAMS



BAKER RIVER DAM SITE 2 - Overview looking upstream





NATIONAL PROGRAM OF INSPECTION OF  
NON FEDERAL DAMS

BAKER RIVER DAM SITE 2  
LOCATION PLAN

Warren, N.H.  
USG Quad. Warren, N.H.

Scale 1:24,000  
0 FEET 3000

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT  
BAKER FLOODWATER RESERVOIR SITE 2

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Howard, Needles, Tammen & Bergendoff has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire Authorization and notice to proceed were issued to Howard, Needles, Tammen & Bergendoff under a letter of March 30, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0060 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Baker Floodwater Reservoir Site 2 (Baker Dam Site 2), also known as David Wayne Hildreth Dam, is located on Berry Brook approximately one mile upstream from the center of Warren, in the Town of Warren, New Hampshire. The dam is shown on U.S.G.S. Quadrangle Warren, New Hampshire, with approximate coordinates of N43°56'24", W71°53'24", Grafton County, New Hampshire. The location of Baker Dam Site 2 is shown on the preceding page.

b. Description of Dam and Appurtenances. Baker Dam Site 2 is an earthen embankment structure. Total length of the dam, according to existing drawings, is 805 feet. Maximum structural height is 84 feet, and the height from the top of dam to the streambed is 68 feet. According to the plans there are three different fill zones in the structure, which include a cutoff wall. Approximately 67 percent of the length of the cutoff wall extends to bedrock. Top width of the dam is 20 feet and the embankment is on a  $2\frac{1}{2}$  horizontal to 1 vertical slope both up and downstream.

Appurtenant structures consist of a concrete riser and pipe principal spillway with a covered top inlet. There are two stages to the inlet structure, a low stage orifice and a high stage covered inlet. The riser discharges through a 4.0 foot diameter concrete pipe and an impact type stilling basin. The emergency spillway is located on the left side of the dam and has a width of 95 feet. It is an excavated earthen structure with a vegetative cover. A 24 inch diameter pond drain pipe can be opened from the riser with a 24 inch diameter gate valve structure to lower the water level.

Figures 1 and 2, located in Appendix B, show a plan of the dam and appurtenant structures. Photographs of each structure are shown in Appendix C.

c. Size Classification. Intermediate (hydraulic height - 68 feet, storage - 2,400 acre-feet) classification based on height being between 40 and 100 feet and storage being between 1,000 acre-feet and 50,000 acre-feet as given in Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The potential for hazard posed by this dam is classified as high. Failure of the dam at maximum pool elevation (top of dam) would probably result in a total flood wave approximately 20 feet high through the center of Warren. About 20 dwellings would probably be inundated. Another 30 structures near the edge of the flooded area may be affected.

e. Ownership. This dam is owned by the New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire.

f. Operator. This dam is maintained and operated by the New Hampshire Water Resources Board. Chairman of the Water Resources Board is Mr. George McGee, Sr.; Mr. Vernon Knowlton is Chief Engineer, Telephone No. 603/271-1110.

g. Purpose of Dam. This dam is used for both flood-water control and recreation. The recreational pool is maintained by the low stage intake in the riser. The storage between the low stage outlet and the emergency spillway crest is used for floodwater control.

h. Design and Construction History. The construction of this dam was completed in September of 1969. Design and construction inspection of this dam were done by the Soil Conservation Service, Durham, New Hampshire. The construction contractor was Windham Roads, Windham, New Hampshire.

i. Normal Operating Procedures. The recreational pool is maintained by the low stage inlet on the riser. Under flood conditions, when the capacity of the low stage orifice is exceeded, the storage is utilized. The high stage outlet will reach maximum design discharge before the reservoir reaches the crest of the emergency spillway. The dam does not require any manual operation in order to function.

### 1.3 Pertinent Data

a. Drainage Area. The area tributary to Baker Dam Site 2 consists of 6.64 square miles of mountainous terrain. The entire watershed is located in the White Mountain National Forest, with little development. Maximum elevation is at about 3500 feet MSL, and reservoir full elevation is at 860 feet.

The area around the reservoir is mostly wooded with some open meadows. There are no cottages or dwellings along the shoreline. Route 25 runs along the right bank of the reservoir.

#### b. Discharge of Dam Site

(1) Outlet works for Baker Dam Site 2 consist of an emergency spillway, a riser with a low stage orifice and a high stage covered top spillway, and a 24 inch pond drain pipe controlled by a gate. Invert of the pond drain is at 807.5 feet. Maximum discharge of the pipe when the reservoir is at the recreational pool level of 834.0 feet is about 87 cfs. The low stage orifice has one opening 36 inch by 23 inches in size set at invert 834.0. Capacity of the low stage inlet when the reservoir is at the crest of the high stage inlet (852.0 ft) is 64 cfs. The high stage covered inlet crest set at elevation 852.0 feet has a capacity of 439 cfs when the water level is at the emergency spillway crest of 861.5 feet. The 95 foot wide emergency spillway has a crest at elevation 861.5 feet. When the water surface is at the top of dam (elevation 870.0) the spillway will have a capacity of 670.6 cfs.

(2) There are no records available of maximum discharge at the site. However, during the inspection of the dam on May 17, 1979 it was noted that debris on the face of the dam reached to about elevation 846.0 which would correspond to a discharge of about 100 cfs.

(3) The spillway and riser capacity with the water surface at the top of the dam is approximately 7200 cfs at elevation 870.0.

(4) Spillway and riser capacity with the water surface elevation at the test flood elevation of 870.8 feet is approximately 8220 cfs.

(5) The total project discharge at the test flood elevation of 870.8 feet is 10,000 cfs.

c. Elevation (feet above MSL)

- (1) Streambed at centerline of dam - 802.0
- (2) Maximum tailwater - unknown
- (3) Upstream portal invert pond drain - 807.5
- (4) Recreation pool - 834.0
- (5) Full flood control pool - 859.6
- (6) Spillway crest (emergency spillway) - 861.5  
(riser crest) - 852.0
- (7) Design surcharge - 859.6
- (8) Top Dam - 870.0
- (9) Test Flood Surcharge - 870.8

d. Reservoir (miles)

- (1) Length of Maximum Pool - .87
- (2) Length of Recreational Pool - .61
- (3) Length of Flood Control Pool - .84

e. Storage (gross acre-feet)

- (1) Recreation Pool - 500
- (2) Flood Control Pool - 1770
- (3) Emergency Spillway Crest Pool - 1880
- (4) Top of Dam - 2400

f. Reservoir Surface (acres)

- (1) Recreation Pool - 37.5
- (2) Flood Control Pool - 60.0
- (3) Emergency Spillway Crest - 61.0
- (4) Test Flood Pool - 68.0
- (5) Top Dam - 68.0

g. Dam

- (1) Type - earth
- (2) Length - 805 feet
- (3) Height - 68 feet hydraulic  
84 feet structural
- (4) Top Width - 20 feet
- (5) Side Slopes - 2½ horizontal to 1 vertical up  
and downstream
- (6) Zoning - 3 zones of fill
- (7) Impervious core - none
- (8) Cutoff - zone 1 fill
- (9) Grout Curtain - none
- (10) Other - none

h. Diversion and Regulating Tunnel

See Section j below.

i. Principal Spillway

- (1) Type - concrete riser, covered top - 4 foot  
diameter discharge pipe through dam.
- (2) Length of Weir - 24 feet total
- (3) Crest Elevation - 852.0
- (4) Gates - none
- (5) U/S Channel - none

### Emergency Spillway

- (1) Type-earth, overflow
- (2) Length of Weir - 95 feet
- (3) Crest Elevation - 861.5
- (4) Gates - none
- (5) U/S Channel - Approach channel from reservoir is 95 feet wide with 2½:1 sides.
- (6) Downstream Channel - The downstream channel is about 15 feet wide. The left bank is relatively flat pasture land. There is a farm house located immediately downstream of the dam. Along the right bank there are scrub trees growing with some of them growing in the channel.

j. Regulating Outlets. The recreation level of the reservoir is controlled by one 36 inch by 23 inch orifice inlets set in the riser at invert elevation 834.0. There is a trash rack for the opening but no control gate. The 24 inch pond drain pipe set at invert 807.5 extends 64 feet into the reservoir from the riser, and has a trash rack at the intake. The pipe is controlled at the riser by a gate.

## SECTION 2 ENGINEERING DATA

### 2.1 Design

A complete set of design data including layout, hydraulic design, foundation and embankment design, geology and soils reports, structural design, quantities and specifications are available for Baker Dam Site 2. In addition, there are construction drawings available. Design of the dam was done by the Soil Conservation Service, Durham, New Hampshire.

### 2.2 Construction

The dam construction was completed in September of 1969. A complete record of construction documents were made available. These documents include; as-built plans, job diaries, surveying records, test drilling logs, compaction test results, concrete tests and certificate of completion. Construction was by Windham Roads, Windham, New Hampshire and was inspected by the Soil Conservation Service, Durham, New Hampshire.

### 2.3 Operation

Normally, the pond drain line gate is closed. The recreational level of 834.0 is maintained by the low stage orifice openings. The principal spillway riser and reservoir storage is designed to retard runoff from up to a 100 year frequency storm without discharge occurring in the emergency spillway (crest 861.5).

### 2.4 Evaluation

a. Availability. Engineering data available for Baker Dam Site 2 consists of the information outlined in Sections 2.1 and 2.2. The plans, design data, and construction records are available at the offices of the Soil Conservation Service, Federal Building, Durham, New Hampshire, 03824.

b. Adequacy. A complete set of design and construction data did allow for a definitive review within the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data reviewed, visual inspection, past performance history and sound engineering judgement.

c. Validity. The field investigation indicated that the external features of Baker Dam Site 2 substantially agree with those shown on the available plans.



SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General. The field inspection of Baker Dam Site 2 was made on May 17, 1979. The inspection team consisted of personnel from Howard, Needles, Tammen & Bergendoff and Geotechnical Engineers, Inc. A representative of the New Hampshire Water Resource Board was also present during the inspection. Inspection checklists, completed during the visual inspection, are included in Appendix A. At the time of inspection the water level was approximately 0.5 feet above the low stage inlet. The upstream face of the dam could only be inspected above this water level.

b. Dam. Visual inspection of the dam indicated that it is in good condition.

The dam consists of an earth embankment about 805 feet long and 68 feet high. The embankment is zoned and has a central core, which is integral with a cut-off trench extending to bedrock. There is a trench drain and blanket drain beneath the downstream section of the embankment.

An unpaved emergency spillway has been cut into the left abutment, and a principal spillway consisting of a drop inlet structure, concrete conduit and outlet structure is located on the approximate center of the embankment.

Upstream Slope

The upstream face was constructed on a slope of 2.5 horizontal to 1 vertical and has a 10 foot wide berm at elevation 834.5, which is 35 feet below the crest. The permanent pool is defined as elevation 834.0 feet, and at the time of inspection the pool was approximately at this elevation.

The upstream slope has a good grass cover, as shown in Photo No. 3. Minor erosion and surface slumping has occurred in the past on the upstream slope near the right abutment contact area which is now well-covered with grass. This area is shown in Photo No. 18.

Crest

The crest of the dam is 20 feet wide and has a sand and gravel roadway, in good condition. Photo No. 5 shows the crest. No significant misalignment of the crest was observed.

### Downstream Slope

The downstream slope is 2.5 horizontal to 1 vertical. The slope shown in Photos No. 6 & 7 is grass covered and generally in good condition. There is an erosion gully at the contact of the slope and the right abutment which is shown in Photo No. 19. The gully has been filled with small boulders at several points along its length, presumably to impede the flow of water. At this time this erosion feature poses no safety problem, but this feature should be examined during future inspections to establish if it is increasing in size.

There is a wet area at the toe of the slope which appears to be due to runoff from a spring on the right abutment about 10 feet from the toe of the embankment at about El 832. The area of this spring is shown in Photo No. 17. The pool elevation at the time of inspection was about 834.5. Since the dam is about 160 feet wide at El 834, it does not seem likely that the spring is a result of seepage through the embankment. This spring and the wet area at the toe of the slope should be closely observed at various reservoir elevations to establish if flow from the spring is related to the reservoir elevation.

Photo No. 15 shows the vegetation that has started to grow along the surface drainage path from the spring to the outlet channel.

At the time of inspection, the water level in the outlet stilling basin was above the outlet pipes of the downstream drainage system, and it could not be determined if water was exiting from these outlets.

c. Appurtenant Structures. Visual inspection of the concrete riser (principal spillway) structure, emergency earth spillway outlet works structure did not reveal any evidence of stability problems. The riser structure generally appeared to be in good condition, except for rust staining, heavy scaling and loss of surface mortar in some locations on the shaft walls.

The spillway trash racks and service ladder are in good condition. Rust was noted only at the manhole cover plate.

The concrete riser (principal spillway) structure consists of three elements; an overflow control with low stage inlet and high stage, covered top crest spillway, a vertical transition and a closed discharge conduit with an impact type stilling basin. The riser structure is placed in the embankment. Visual inspection revealed that the riser structure appeared to be in good condition, except for rust staining, extensive surface scaling, cracks and loss of surface mortar in some locations. Loss of coarse aggregate particales were noted, Photos No. 8,9,10,11 & 12.

The trash racks at the low and high stage intakes of the principal spillway consist of standard shape angles and grating. Both trash rack assemblies are in good condition. No rust or peeling of the protective coating were noted.

The emergency earth spillway is a large relatively flat grassy area located at the left abutment.

The upstream channel, viewed from the axis, is shown in Photo No. 21 and the downstream channel from the dam is shown in Photo No. 20. Photo No. 16 shows a wet area at the toe of the cut slope forming the right wall of the spillway. This area is about 100 feet downstream from the dam axis.

The pond drain pipe, intake structure and gate could not be inspected as it was under water. The operating mechanism appeared to be in good condition.

The outlet works structure at the toe of the dam consisting of 48 inch reinforced concrete pipe and stilling basin structure is located at the original stream channel, Photos No. 13 & 14. The apron slab and training walls of the stilling basin structure appear to be in sound condition. Some water staining and concrete spalling were noted at the discharge pipe area.

Visual inspection of discharge, Photo No. 22 channel showed it to be in good condition. There appeared to be minimum obstructions to free flow.

d. Reservoir Area. The area around the reservoir is mostly wooded with some open meadows. There are no cottages or dwellings along the shoreline. Route 25 runs along the right bank of the reservoir. Debris was noted on the upstream face of the dam to 10 to 12 feet above the water surface at the time of inspection.

e. Downstream Channel. The downstream channel is about 15 feet wide. The left bank is relatively flat pasture land. There is a farm house located immediately downstream of the dam, Photo No. 22. Along the right bank there are scrub trees growing, with some of them growing in the channel. A beaver dam across the stream diverts flow from the channel to the farm land.

### 3.2 Evaluation

Visual examination indicates the dam is in good condition. The inspection of the dam revealed the following:

- (a) Some staining, scaling and cracking of the concrete surface of the riser.
- (b) Some water staining and concrete spalling around the 4 foot diameter outlet pipe.
- (c) A minor spring of clear water on the right abutment.
- (d) Minor surface erosion gully at the juncture of the downstream slope and the right abutment.

SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedure

Baker Dam Site 2 is used for floodwater control and recreation. Under normal operating procedures the dam is left to function as designed. The recreation pool level is maintained by the low stage orifice openings in the riser. Flood events of up to a 100 year frequency are retarded by the reservoir storage between the recreation pool and the emergency spillway crest. The emergency spillway is utilized only with events greater than a 100 year frequency.

4.2 Maintenance of Dam

The dam is inspected on an annual basis by the New Hampshire Water Resources Board and the Soil Conservation Service. Maintenance is undertaken as a result of the inspection on an as needed basis. The dam is visited on a monthly basis by personnel of the Water Resources Board.

4.3 Maintenance of Operating Facilities

Maintenance of the outlet works is performed as in Section 4.2.

4.4 Description of Warning Systems

There are no warning systems in effect for this facility.

4.5 Evaluation

The current operation and maintenance procedures for this facility appear to be adequate to insure that any problems encountered can be remedied within a reasonable period of time. However, the owner should establish a downstream warning system to follow in the event of emergency conditions.

SECTION 5  
HYDROLOGY AND HYDRAULIC ANALYSIS

5.1 Evaluation of Features

a. General. Baker Dam Site 2 is an earthen embankment dam 805 feet long with a hydraulic height of 68 feet. The dam is constructed with three fill zones and an earth fill core which extends to bedrock over a portion of the length of the dam. Appurtenant works consist of a two stage riser and 4 foot diameter concrete pipe which discharges to an impact type stilling basin, an emergency spillway 95 feet wide and a 24 inch diameter gated pond drain.

The dam is used for floodwater control and recreation. The dam is classified as intermediate in size having a height of 68 feet and maximum storage of 2,400 acre-feet.

b. Design Data. According to the Soil Conservation Service design data, this dam is constructed to retard flood flows of up to a 100 year frequency storm without utilizing the emergency spillway. The design flood control elevation is 859.6 feet or 1.9 feet below the emergency spillway crest. Total runoff for this condition is 3.91 inches, during a six hour Type IIB storm. The crest of the dam was designed using a total watershed runoff of 10.84 inches. The structure is classified as having a "C" hazard which is defined as "dams located where failure may cause loss of life, serious damage to homes, industrial and commercial buildings, important public utilities, main highways, or railroads.

c. Experience Data. There are no records available of maximum discharge at the dam site. However, during the inspection of the dam on May 17, 1979, it was noted that debris on the face of the dam reached to about elevation 846.0 which would correspond to a discharge of about 100 cfs.

d. Visual Observations. No evidence of damage to any portion of the project from overtopping was visible at the time of inspection.

e. Test Flood Analysis. Even though detailed design and operational data are available for this dam, a hydrologic evaluation was performed using a test flood equal to the Probable Maximum Flood (PMF) as determined from Guide Curves issued by the Corps of Engineers. Based on a drainage area of 6.64 square miles, it was estimated that the test flood inflow at Baker Dam Site 2 would be 14,100 cfs. Following the guidance for Estimating Effect of Surcharge Storage on Maximum Probable Discharge results in a routed test flood

outflow of 10,000 cfs. As the maximum capacity of the spillways at the top of dam is 6,706 cfs (approximately 67 percent of the routed test flood outflow), the test flood will result in the dam being overtopped by approximately 0.8 feet.

As there is a high hazard to loss of life from large flows downstream of the dam (resulting from dam failure), and dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream from the dam. A review using  $\frac{1}{2}$  the PMF was made. This analysis indicates that the test flood inflow would be approximately 7,050 cfs. Following the guidance for Estimating Effect of Surcharge Storage on Maximum Probable Discharge results in a routed  $\frac{1}{2}$  PMF outflow of 3,460 cfs. As the total capacity of the spillways at the top of dam is 6,706 cfs, the spillway can safely pass the routed  $\frac{1}{2}$  PMF outflow with a freeboard of approximately 3.0 feet.

f. Dam Failure Analysis. The impact of failure of the dam at maximum pool (top of dam) was assessed using the "Rule of Thumb" Guidance for Estimating Downstream Hazard Hydrographs issued by the Corps of Engineers. The analysis covered the reach extending from the dam to a point 3.3 miles downstream on the Baker River. Prior to breach of dam, the downstream river stage would be about 7.5 feet with the spillway at full capacity. Failure of the dam with the water surface at the top of dam would probably result in a flood wave stage of approximately 20 feet in the center of Warren. This flood stage would be reduced to about 16 feet in height at the Route 25 crossing of the Baker River 3.3 miles downstream of the dam. The main portion of the flood wave would probably inundate about 20 dwellings in the reach studied. In addition, there are another 30 dwellings in fringe areas that may experience flooding by the flood wave.

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observation. The visual examination did not disclose an immediate stability problem.

b. Design and Construction Data. Design drawings and construction specifications Baker Dam Site 2 indicate the dam is a zoned embankment consisting of a central impervious core with a cut-off trench extending to bedrock.

The upstream slope is 2.5 horizontal and 1 vertical with a 10 foot wide berm at about mid-height.

The downstream slope is 2.5 horizontal to 1 vertical and has no berm.

There is a foundation drainage trench and blanket drain beneath the downstream portion of the embankment.

An emergency, grass-covered spillway passes around the embankment on the left abutment.

Construction records indicate that the dam and appurtenant structures were built according to the plans and specifications.

c. Operating Records. No operating records are available.

d. Post-Construction Changes. There is no record of post-construction changes.

e. Seismic Stability. This dam is located in Seismic Zone 2 and in accordance with recommended Phase 1 guidelines does not warrant seismic analysis.



SECTION 7  
ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection of Baker Dam Site 2 indicates the dam is in good condition. The inspection revealed the following:

- (1) Some staining, scaling, and cracking of the concrete surface of the riser.
- (2) Some water staining and concrete spalling around the 4 foot diameter outlet pipe.
- (3) A minor spring of clear water on the right abutment.
- (4) Minor surface erosion gully at the juncture of the downstream slope and the right abutment.

The hydraulic analysis indicates that the spillway cannot pass the routed test flood without overtopping the dam.

b. Adequacy of Information. A complete set of design and construction data did allow for a definitive review with the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data reviewed, visual inspection, past performance history and sound engineering judgement.

c. Urgency. This dam is in generally good condition. The recommendations and remedial measures described in Sections 7.2 and 7.3 should be accomplished within 2 years after receipt of this Phase I Inspection Report by the owner.

d. Necessity of Additional Investigation. No additional investigation is needed to complete the Phase I inspection.

7.2 Recommendations

There are no recommendations resulting from the Phase I inspection.

7.3 Remedial Measures

- (a) Repair the concrete surface of the riser structure.
- (b) Repair the concrete spalling at the end of the 4 foot diameter discharge pipe.
- (c) Observe and record the condition of the spring on the right abutment with changing reservoir level. It is particularly important that these observations be made during the next filling of the reservoir.

(d) The brush and small trees that have started to grow just downstream of the dam toe should be cleared to the edge of the woods to permit observation of potential seepage in this area.

(e) The erosion gully at the right abutment contact should be observed to determine if this condition has stabilized. If continued erosion is noted, this gully should be paved.

(f) Devise a warning system to follow in the event of emergency conditions.

(g) Continue the periodic inspection on a biennial basis.

(h) Establish a system such that the reservoir level can be monitored during periods of intense rainfall.

#### 7.4 Alternatives

There are no practical alternatives to the remedial measures outlined in Section 7.3.

**APPENDIX A**  
**INSPECTION CHECKLIST**

VISUAL INSPECTION CHECK LIST  
PARTY ORGANIZATION

A-1

PROJECT SITE 2, BAKER DAM

DATE May 17, 1979

TIME 9:15 AM

WEATHER Fair

W.S. ELEV. 834.8 U.S. - DN.S

PARTY:

1. <u>G. Slaney</u>	<u>HNTB</u>	6. <u></u>
2. <u>S. Mazur</u>	<u>HNTB</u>	7. <u></u>
3. <u>D. LaGatta</u>	<u>GEI</u>	8. <u></u>
4. <u>C. Osgood</u>	<u>GEI</u>	9. <u></u>
5. <u></u>		10. <u></u>

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Dam</u>	<u>D. LaGatta , C. Osgood</u>	
2. <u>Spillway, Outlet Works</u>	<u>S. Mazur</u>	
3. <u>and Downstream Channel</u>	<u>G. Slaney</u>	
4. <u></u>		
5. <u></u>		
6. <u></u>		
7. <u></u>		
8. <u></u>		
9. <u></u>		
10. <u></u>		

## PERIODIC INSPECTION CHECK LIST

A-2

PROJECT BAKER RIVER WATERSHED DAM #2 DATE May 17, 1979  
PROJECT FEATURE \_\_\_\_\_ NAME \_\_\_\_\_  
DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

## AREA EVALUATED

## CONDITION

DAM EMBANKMENT

Crest Elevation	870.0
Current Pool Elevation	834.8
Maximum Impoundment to Date	846.0 estimated from debris level.
Surface Cracks	None observed
Pavement Condition	Gravel road on crest
Movement or Settlement of Crest	None apparent
Lateral Movement	None apparent
Vertical Alignment	No misalignment noticeable
Horizontal Alignment	No misalignment noticeable
Condition at Abutment and at Concrete Structures	Good except for wet patch at downstream right abutment
Indications of Movement of Structural Items on Slopes	No structural items on slopes
Trespassing on Slopes	No damage from trespass
Sloughing or Erosion of Slopes or Abutments	Minor erosion gully on upstream slope now well grassed over
Rock Slope Protection - Riprap Failures	Riprap only at outlet works; becoming covered with vegetation
Unusual Movement or Cracking at or near Toes	None observed
Unusual Embankment or Downstream Seepage	Some water on right abutment slope appears to originate at about El. 832 ft.
Piping or Boils	None observed
Foundation Drainage Features	Exits of drains are clear and open
Toe Drains	None exist
Instrumentation System	None exist
Vegetation	Good grass cover

## PERIODIC INSPECTION CHECK LIST

A-3

PROJECT SITE 2, BAKER DAMDATE May 17, 1979PROJECT FEATURE Intake Channel/StructureNAME D. LaGatta, C. OsgoodDISCIPLINE Geotechnical, Structural, EngineersNAME S. Mazur

## AREA EVALUATED

## CONDITION

OUTLET WORKS - INTAKE CHANNEL AND  
INTAKE STRUCTURE

## a. Approach Channel

None observed

Slope Conditions

Bottom Conditions

Rock Slides or Falls

Log Boom

None

Debris

Some debris at low trash rack.  
(Riser structure)

Condition of Concrete Lining

Drains or Weep Holes

## b. Intake Structure

Concrete of riser structure at spill-  
way intake openings is in good condi-  
tion. Bottom water release structure  
was under water.

Condition of Concrete

Stop Logs and Slots

## PERIODIC INSPECTION CHECK LIST

A-4

PROJECT SITE 2, BAKER DAM DATE May 17, 1979  
PROJECT FEATURE Control Tower NAME G. Slaney  
DISCIPLINE Structural/Hydraulic Engineers NAME S. Mazur

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	Outlet works (bottom water release structure) consist of inlet structure with trash rack and 24" ID reinforced concrete pipe extended to riser structure. Outlet works structure is controlled by mechanically operated gate.
Condition of Joints	
Spalling	
Visible Reinforcing	
Rusting or Staining of Concrete	
Any Seepage or Efflorescence	
Joint Alignment	
Unusual Seepage or Leaks in Gate Chamber	
Cracks	
Rusting or Corrosion of Steel	
b. Mechanical and Electrical	
Air Vents	Mechanically operated gate and control mechanisms are housed in riser structure. Gate is operated from roof of riser structure. Gate and control mechanisms appear to be in good operational condition.
Float Wells	
Crane Hoist	
Elevator	
Hydraulic System	
Service Gates	
Emergency Gates	
Lightning Protection System	
Emergency Power System	
Wiring and Lighting System	

## PERIODIC INSPECTION CHECK LIST

A-5

PROJECT SITE 2, BAKER DAMDATE May 17, 1979PROJECT FEATURE Spillway/Outlet Works ConduitNAME G. SlaneyDISCIPLINE Structural/Hydraulic EngineersNAME S. Mazur

## AREA EVALUATED

## CONDITION

OUTLET WORKS - TRANSITION AND CONDUIT

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

At the time of inspection outlet conduits were under water. Outlet conduit (dam section) consists of 48" ID reinforced concrete pipe and is placed on concrete bedding. Outlet works conduit appears to be in good condition.



## PERIODIC INSPECTION CHECK LIST

A-6

PROJECT SITE 2, BAKER DAMDATE May 17, 1979PROJECT FEATURE Outlet Structure/ChannelNAME D. LaGatta, C. OsgoodDISCIPLINE Structural/Hydraulic/GeotechnicalNAME S. Mazur, G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Concrete outlet works pipe and discharge channel including training walls are in good condition.
Rust or Staining	Water staining
Spalling	Some loss of concrete at concrete wall around discharge pipe.
Erosion or Cavitation	None
Visible Reinforcing	None
Any Seepage or Efflorescence	None
Condition at Joints	Good
Drain Holes	Water of channel above invert of drains so flow not apparent
Channel	Rock floored stream
Loose Rock or Trees Overhanging Channel	None
Condition of Discharge Channel	Clear except for brush encroaching on channel about 175 ft downstream

## PERIODIC INSPECTION CHECK LIST

A-7

PROJECT SITE 2, BAKER DAM

DATE \_\_\_\_\_

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p> <p>a. Approach Channel</p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Approach Channel</p> <p>b. Weir and Training Walls</p> <p>General Condition of Concrete</p> <p>Rust or Staining    Some rust staining</p> <p>Spalling</p> <p>Any Visible Reinforcing    None</p> <p>Any Seepage or Efflorescence    None</p> <p>Drain Holes</p> <p>c. Discharge Channel</p> <p>General Channel</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Channel</p> <p>Other Obstructions</p>	<p>Good condition, gravel road crosses approach</p> <p>None</p> <p>None</p> <p>Grass covered</p> <p>This facility has two spillway structures; principal concrete riser or shaft spillway and emergency earth spillway located in left abutment. Both spillways generally are in good condition.</p> <p>Some scaling - loss of surface mortar and in some locations loss of coarse aggregate particles. (Photo No. 12)</p> <p>Generally good, some wet areas</p> <p>None</p> <p>None</p> <p>Wet area at base of cut slope, covered with vegetation</p> <p>None</p>

## PERIODIC INSPECTION CHECK LIST

A-8

PROJECT SITE 2, BAKER DAM

DATE May 17, 1979

PROJECT FEATURE

NAME

DISCIPLINE

NAME

## AREA EVALUATED

## CONDITION

OUTLET WORKS - SERVICE BRIDGE

## a. Super Structure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

## b. Abutment &amp; Piers

General Condition of Concrete

Alignment of Abutment

Approach to Bridge

Condition of Seat &amp; Backwall

This facility has no service bridge.

APPENDIX B  
ENGINEERING DATA

1. LIST OF DESIGN, CONSTRUCTION AND MAINTENANCE  
RECORDS
2. PAST INSPECTION REPORTS
3. PLAN AND DETAILS

AVAILABLE ENGINEERING DATA

1. A set of drawings (24 sheets), dated November 1965, showing plans and details of the dam and appurtenant structures.
2. Design Data: including layout, hydraulic design, geology and soils reports, structural design, quantities and specifications.
3. Construction Data: including as-built plans, job diaries, surveying records, test drilling logs, compaction test results, concrete tests, and certificate of completion.

All of the above are on file with the U.S.D.A. Soil Conservation Service, Federal Building, Durham, N.H. 03824.

PAST INSPECTION REPORTS

# MAINTENANCE CHECKLIST FOR PL 566 FLOOD CONTROL STRUCTURES

This maintenance checklist is a guide for determining the maintenance required for Public Law 566 flood control structures in New Hampshire. It doesn't take the place of experience and judgment and is not inclusive. Items of a difficult nature to check, such as principal spillway conduit condition, are not included. Intensive checks of these items are necessary at proper intervals. Review of s Built drawings, the design folder, structure history, and previous maintenance reports should be part of the inspection. Prompt maintenance is a vital part of safe and effective operation.

except where otherwise indicated, completion of this form may be facilitated by ranking maintenance items on a 1 to 4 basis where

- 1 = satisfactory
- 2 = satisfactory, but check carefully at next inspection
- 3 = requires maintenance this season
- 4 = requires immediate attention.

244.10

WATERSHED Baker SITE 2 DATE 6-13-78  
 INSPECTED BY Garv Kerr, Lyall Milligan (WRB); Mike Dannehy, Nick Luhtala, Ray Wenninger  
 (SES)

## 1. GENERAL ITEMS

Access Road.	.	.	.	.	.	.	.	.	.	3
Site Fencing.	.	.	.	.	.	.	.	.	.	1
Traffic Conditions.	.	.	.	.	.	.	.	.	.	1
Vandalism Control.	.	.	.	.	.	.	.	.	.	1
Trash Control.	.	.	.	.	.	.	.	.	.	1

COMMENTS Replace cable across top of dam at spillway and posts. General appearance good.

## RESERVOIR

Timber stand at reservoir.	.	.	.	.	.	.	.	.	1
Debris and slash.	.	.	.	.	.	.	.	.	3
Sediment level in relation to low stage inlet	.	.	.	.	.	.	.	.	1

COMMENTS Some debris at riser should be removed.

### 3. EMBANKMENT AND EXCAVATED SLOPES

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	Dam	ES Dike	Emergency Spillways <sup>1/</sup>		Other	
			left	right	( )	( )
Sliding or sloughing	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Holes (rodent and other) (check especially at embankments)	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Excessive settlement (embankments)	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Cracks						
Traverse	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Longitudinal	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Seepage <sup>2/</sup>	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—
Piping <sup>2/</sup>	<u>1</u>	<u>1</u>	<u>1</u>	—	—	—

COMMENTS \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

### 4. RIPRAP

	Displ. of Rock	Loss of Spalls	Loss of Bedding	Erosion of Found.	Break- down of Rock
Dam					
Upstream berm	—	—	—	—	—
Principal Spillway Outlet	<u>1</u>	—	—	—	—
Embankment Gutters					
left	—	—	—	—	—
right	—	—	—	—	—
Emergency Spillway					
location _____	—	—	—	—	—
location _____	—	—	—	—	—
Waterways					
location 2d berm outlet	<u>3</u>	—	—	—	—
location _____	—	—	—	—	—
Outlet Channel	—	—	—	—	—
Other _____	—	—	—	—	—

COMMENTS Need a little rock and replacement at 2d berm outlet--not a big job.

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

<sup>1/</sup>Looking downstream.

<sup>2/</sup>Check especially at downstream face of embankments.



## 5. VEGETATION

	Dam	Emergency Spillways <sup>1/</sup>		Dike	Outlet Channel	Water way	Other (1st ES Berm)
Condition of stand (including need for lime and fertilizer)	—	—	—	—	—	—	—
Undesirable vegetation	—	(3)	—	—	—	—	—
Drainage (surface)	—	(4)	—	—	—	—	—
Erosion <sup>2/</sup>	(3)	—	—	—	—	—	3
Sedimentation	—	—	—	—	—	—	—
Condition of planting	—	—	—	—	—	—	—
Pest control	—	—	—	—	—	—	—
Fire control	—	—	—	—	—	—	—

COMMENTS Spillway floor wetter than before. Vegetation dying out, scouring on outlet from water needs immediate attention. General vegetation on dam and trees look good. Brush on plunge pool outlet. Left downstream slope gutter needs 6"-12" rock, about 1' wide. Recommend a little rock at 1st berm outlet

## 6. EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam <sup>1/</sup>		Other	
		left	right	(lower ES drain)	(upper ES drain)
Depth of Flow	With any obstruction	—	—	—	—
(in inches above invert)	Without any obstruction	3/8"	3/8"	1/2"	1/2"
Turbidity of Discharge	With any obstruction	—	—	no	—
(yes, no)	Without any obstruction	no	no	no	no
Condition of Protective Coating	Outside	1	1	1	1
	Inside	—	—	—	1
Obstruction in Flow		no	no	yes	no
(yes, no)					
Animal Guard Condition		—	—	1	1
Outlet Condition		1	1	1	3
Retarding Pool Elevation (ft. msl)	_____ or Approx. 1 (ft.)			above	normal pool
Other	_____			below	

COMMENTS Spillway drain at ES floor partially plugged with pie plate. Removed it. Drain is okay. 1/2" depth of flow. No erosion at this outlet. Manholes on berm okay from exterior and listening to running water inside. Road culverts (up and downstream) appear okay.

<sup>1/</sup>Looking downstream.

<sup>2/</sup>Including wave, surface, stream, manmade, and livestock erosion.

7. RISER

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery.  
Use safety harness.

Ladders:  
inside and out

Condition of protective coating\_\_\_;  
Corrosion\_\_\_; Damaged parts\_\_\_; Loose\_\_\_;  
Other\_\_\_.

Concrete:  
~~inside~~ and out

Cracking /; Spalling /; Other deterioration /; Excessive movement (check joint at riser and conduit)\_\_\_; Other\_\_\_.

Trashracks:  
low and high stage

Condition of protective coatings\_\_\_; Corrosion /; Damaged parts /; Condition of fastenings /; Need of gratings due to beaver\_\_\_; Safety condition (protruding fastenings, sharp edges, etc.)\_\_\_; Other\_\_\_.

Manhole:

Condition of protective coatings\_\_\_; Corrosion \_\_\_; Damage\_\_\_; Lock operable\_\_\_; Other\_\_\_.

Gate:  
including lifting  
device, stem, guides,  
disc

Condition of protective coating\_\_\_; Corrosion \_\_\_; Damaged parts\_\_\_; Condition of fastenings\_\_\_; Stem alignment\_\_\_; Lubrication\_\_\_; Operation\_\_\_; Other\_\_\_.

Safety Items:

Condition of warning signs\_\_\_; Condition of safety equipment\_\_\_; Other\_\_\_.

COMMENTS Did not go down riser. Suggest interior of riser and gate operation be checked at regular intervals.

---



---



---



---



---

IMPACT BASIN, SAF. BOX INLET, & MISCELLANEOUS CONCRETE STRUCTURES

(specify) IMPACT BASIN

Concrete:                      Cracking 1; Spalling 1; Other deterioration  
inside and out                      1; Excessive movement (check joints)\_\_\_;  
Waterstops\_\_\_; Joint sealant\_\_\_; Other\_\_\_.

Trashracks:                      Condition of protective coatings\_\_\_; Corrosion  
low and high stage                      \_\_\_; Damaged parts\_\_\_; Condition of fasten-  
ings\_\_\_; Need of gratings due to beaver\_\_\_;  
Safety condition (protruding fastenings, sharp  
edges, etc.)\_\_\_; Other\_\_\_.

Gates:                              Condition of protective coating\_\_\_; Corrosion  
including lifting                      \_\_\_; Damaged parts\_\_\_; Condition of fasten-  
device, stem, guides,                      ings\_\_\_; Stem alignment\_\_\_; Operation\_\_\_;  
disc, flap                              Lubrication\_\_\_; Wood decay\_\_\_; Other\_\_\_.

Structure Drainage:              Report under "Embankment and Other Drains"

Structure, Railing,              Condition of protective coating 1; Corrosion  
Grates, Barriers,                      1; Damaged parts 1; Condition of Fasten-  
etc.      Fence                      ings 1; Wood decay\_\_\_; Safety condition  
(protruding fastenings, sharp edges, etc.)  
\_\_\_; Other\_\_\_.

Safety Items:                      Condition of warning signs\_\_\_; Condition of  
safety equipment\_\_\_; Other\_\_\_.

COMMENTS \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

9. CHANNEL

Stream obstructions.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Debris in stream.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Sediment bars controlled.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Plunge pool stability.	.	.	.	.	.	.	.	.	.	.	___
Fish habitat appurtenances	.	.	.	.	.	.	.	.	.	.	___
Riprap -- Report under "Riprap" (item 4)											___

COMMENTS \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4. 4. 4. 4. 4.

—

1. The first part of the document is a letter from the President of the United States to the Secretary of the Navy, dated 18th March 1899. The letter is addressed to the Secretary of the Navy, Department of the Navy, Washington, D.C. The letter is signed by the President of the United States, William McKinley.

:

— 11 —

CONFIDENTIAL

EMBANKMENT AND EXCAVATED SLOPE

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	<u>EM.SP</u>		Emergency Spillways		<u>DOWNSTREAM</u> <u>WASTE</u> <u>(GREEN)</u> <u>AT SIDE</u>	<u>Other</u> <u>( )</u>
	<u>Dam</u>	<u>Dike</u>	<u>left</u>	<u>right</u>		
Sliding or sloughing	<u>1</u>	<u>1</u>	<u>1</u>	<u>—</u>	<u>1</u>	<u>—</u>
Holes (rodent and other) (check especially at embankments)	<u>1</u>	<u>1</u>	<u>1</u>	<u>—</u>	<u>1</u>	<u>—</u>
Excessive settlement (embankments)	<u>1</u>	<u>1</u>	<u>1</u>	<u>—</u>	<u>1</u>	<u>—</u>
Cracks						
Traverse	<u>1</u>	<u>1</u>	<u>1</u>	<u>—</u>	<u>1</u>	<u>—</u>
Longitudinal	<u>1</u>	<u>1</u>	<u>1</u>	<u>—</u>	<u>1</u>	<u>—</u>
Seepage <u>2/</u>	<u>1</u>	<u>1</u>	<u>2</u>	<u>—</u>	<u>2</u>	<u>—</u>
Piping <u>2/</u>	<u>1</u>	<u>1</u>	<u>2</u>	<u>—</u>	<u>1</u>	<u>—</u>

COMMENTS SMALL GULLY ALONG DOWNSTREAM TOE ON LEFT SIDE OF  
STREAM SHOULD BE WATCHED. THE OUTLET OF THIS GULLY  
INTO THE STREAM HAS BEEN RIPRAPPED. THIS NEEDS  
WATCHING, TOO. TWO SEEP AREAS ON DOWNSTREAM TOE OF  
WASTE AREA. SEEPAGE OCCURRING ALONG TOE OF EM.  
SPILLWAY SLOPE IN EXIT CHANNEL. ALSO PILES OF FINES

4. RIPRAP

	<u>Displ.</u> <u>of</u> <u>Rock</u>	<u>Loss</u> <u>of</u> <u>Spalls</u>	<u>Loss</u> <u>of</u> <u>Bedding</u>	<u>Erosion</u> <u>of</u> <u>Found.</u>	<u>Break-</u> <u>down</u> <u>of Rock</u>
Dam					
Upstream berm	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Principal Spillway Outlet	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Embankment Gutters					
left	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
right	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Emergency Spillway					
location <u>                    </u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
location <u>                    </u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Waterways					
location <u>ACCESS RD</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>
location <u>BERM</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>
Outlet Channel	<u>2</u>	<u>2</u>	<u>2</u>	<u>1</u>	<u>1</u>
Other <u>                    </u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>

COMMENTS REMOVE WOODY GROWTH FROM WATERWAY  
AT END OF ACCESS ROAD CULVERT

1/Looking downstream.

2/Check especially at downstream face of embankments.

VEGETATION

	Dam	Emergency Spillways <sup>1/</sup>		Dike	Outlet Channel	Water way	Other ( )
Condition of stand (including need for lime and fertilizer)	<u>1</u>	<u>1</u>	<u>—</u>	<u>—</u>	<u>1</u>	<u>—</u>	<u>—</u>
Undesirable vegetation	<u>1</u>	<u>1</u>	<u>—</u>	<u>—</u>	<u>2</u>	<u>—</u>	<u>—</u>
Drainage (surface)	<u>NA</u>	<u>2</u>	<u>—</u>	<u>—</u>	<u>NA</u>	<u>—</u>	<u>—</u>
Erosion <sup>2/</sup>	<u>1</u>	<u>2</u>	<u>—</u>	<u>—</u>	<u>1</u>	<u>—</u>	<u>—</u>
Sedimentation	<u>1</u>	<u>1</u>	<u>—</u>	<u>—</u>	<u>1</u>	<u>—</u>	<u>—</u>
Condition of planting	<u>NA</u>	<u>2</u>	<u>—</u>	<u>—</u>	<u>NA</u>	<u>—</u>	<u>—</u>
Pest control	<u>1</u>	<u>1</u>	<u>—</u>	<u>—</u>	<u>NA</u>	<u>—</u>	<u>—</u>
Fire control	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>

COMMENTS DRAINAGE WILL BE NECESSARY IN ORDER TO  
KEEP A SATISFACTORY GRASS SOD ON OUTLET END  
OF EMERGENCY SPILLWAY.

GROWN VETCH SPREADING OVER DAM FACES. TREEFOL THINNING

6. EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam <sup>1/</sup>		Other <sup>EM.SP FLOOR DRAIN</sup>
		left	right	( ) ( )
Depth of Flow	With any obstruction	<u>—</u>	<u>—</u>	<u>3</u>
(in inches above invert)	Without any obstruction	<u>1/2</u>	<u>1/2</u>	<u>2</u>
Turbidity of Discharge	With any obstruction	<u>NO</u>	<u>NO</u>	<u>1</u>
(yes, no)	Without any obstruction	<u>NO</u>	<u>NO</u>	<u>—</u>
Condition of Protective	Outside	<u>1</u>	<u>1</u>	<u>2</u>
Coating	Inside	<u>1</u>	<u>1</u>	<u>2</u>
Obstruction in Flow		<u>NO</u>	<u>NO</u>	<u>YES</u>
(yes, no)				
Animal Guard Condition		<u>1</u>	<u>1</u>	<u>—</u>
Outlet Condition		<u>1</u>	<u>1</u>	<u>1</u>
Retarding Pool Elevation (ft. msl)	_____ or _____ (ft.) above			
Other	_____ below			

COMMENTS THERE IS A 3/4 IN. Ø PIPE INSTALLED IN THE OUTLET  
END OF THE EM. SP. FLOOR DRAIN.

<sup>1/</sup>Looking downstream.

<sup>2/</sup>Including wave, surface, stream, manmade, and livestock erosion.

RISER

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery. Use safety harness.

Ladders:  
inside and out

Condition of protective coating\_\_\_;  
Corrosion\_\_\_; Damaged parts\_\_\_; Loose\_\_\_;  
Other\_\_\_.

Concrete:  
inside and out

Cracking\_\_\_; Spalling\_\_\_; Other deterioration\_\_\_; Excessive movement (check joint at riser and conduit)\_\_\_; Other\_\_\_.

Trashracks:  
low and high stage

Condition of protective coatings\_\_\_; Corrosion\_\_\_; Damaged parts\_\_\_; Condition of fastenings\_\_\_; Need of gratings due to beaver\_\_\_; Safety condition (protruding fastenings, sharp edges, etc.)\_\_\_; Other\_\_\_.

Manhole:

Condition of protective coatings\_\_\_; Corrosion\_\_\_; Damage\_\_\_; Lock operable\_\_\_; Other\_\_\_.

Gate:  
including lifting  
device, stem, guides,  
disc

Condition of protective coating\_\_\_; Corrosion\_\_\_; Damaged parts\_\_\_; Condition of fastenings\_\_\_; Stem alignment\_\_\_; Lubrication\_\_\_; Operation\_\_\_; Other\_\_\_.

Safety Items:

Condition of warning signs\_\_\_; Condition of safety equipment\_\_\_; Other\_\_\_.

COMMENTS WRB PERSONNEL WILL CHECK RISER AND APPURTENANCES LATER. THE TOP OF THE RISER IS STAINED. IT APPEARS THAT SOMEONE MAY HAVE BUILT A FIRE ON THE TOP SLAB. THE STAIN CONTINUES DOWN THE FRONT FACE OF THE RISER. THE CONCRETE SHOULD BE CHECKED FOR DAMAGE.

IMPACT BASIN, SAF. BOX INLET, & MISCELLANEOUS CONCRETE STRUCTURES(specify) IMPACT BASIN

Concrete:                      Cracking 1; Spalling 2; Other deterioration  
inside and out              2; Excessive movement (check joints) 1;  
Waterstops 1; Joint sealant 1; Other    .

Trashracks:                      Condition of protective coatings    ; Corrosion  
low and high stage                 ; Damaged parts    ; Condition of fasten-  
ings    ; Need of gratings due to beaver    ;  
Safety condition (protruding fastenings, sharp  
edges, etc.)    ; Other    .

Gates:                              Condition of protective coating    ; Corrosion  
including lifting                 ; Damaged parts    ; Condition of fasten-  
device, stem, guides,              ings    ; Stem alignment    ; Operation    ;  
disc, flap                      Lubrication    ; Wood decay    ; Other    .

Structure Drainage:              Report under "Embankment and Other Drains"

Structure, Railing,              Condition of protective coating 1; Corrosion  
Grates, Barriers,              1; Damaged parts 1; Condition of Fasten-  
etc.                              ings 1; Wood decay    ; Safety condition  
(protruding fastenings, sharp edges, etc.)  
1; Other    .

Safety Items:                      Condition of warning signs    ; Condition of  
safety equipment    ; Other    .

COMMENTS THERE IS SOME SPALLING AROUND THE  
P.S. PIPE. THERE IS A ROCK MARK ON THE  
TOP SURFACE OF THE BAFFLE

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

9 CHANNEL

Stream obstructions.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Debris in stream.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Sediment bars controlled.	.	.	.	.	.	.	.	.	.	.	<u>2</u>
Plunge pool stability.	.	.	.	.	.	.	.	.	.	.	<u>1</u>
Fish habitat appurtenances	.	.	.	.	.	.	.	.	.	.	<u>   </u>
Riprap -- Report under "Riprap" (item 4)											

COMMENTS \_\_\_\_\_


\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_


\_\_\_\_\_






10-17-68

2/27/73 2 Baker 110/73 500



PLAN

192



LEGEND

- ② INDICATES LOCATION WHERE PHOTO WAS TAKEN AND DIRECTION


PLAN

1 THE INFORMATION SHOWN ON THESE DRAWINGS IS BASED ON THE ORIGINAL CONSTRUCTION PLANS AND VISUAL OBSERVATIONS MADE DURING THE FIELD INSPECTION. DIMENSIONS OR MATERIALS INDICATED ON THESE DRAWINGS WHICH WERE BELOW GRADE OR WATER DURING THE TIME OF INSPECTION WERE NOT VERIFIED


2 THE ELEVATIONS SHOWN ARE 1929 MSL DATUM

PROJECT NUMBER: 70014-1-00000000	U.S. ARMY ENGINEER DISTRICT (NEW ENGLAND)
DISTRICT: BOSTON, MASS.	NAME OF DAM: BAKER
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
SITE NO. 2	
BAKER FLOODWATER RESERVOIR	

Figure 1 of 2




SECTION




SECTION B-B

1973



SECTION A-A





SECTION C-C

1. THE INFORMATION SHOWN  
BASED ON THE ORIGINAL  
AND VISUAL OBSERVATION  
FIELD INSPECTION DONE  
INDICATED ON THESE OR  
BELOW GRADE OR WATER  
INSPECTION WERE NOT V  
2. THE ELEVATIONS SHOWN

EARTH FILL REQUIREMENTS			
ZONE	MATERIAL	REQUIRED WATER CONTENT	COMPACTION DEFINITION
1	SAND, SILTY, FINE	OPTIMUM TO +4% OF OPTIMUM	100% MAXIMUM DENSITY BY ASTM D698 METHOD A
2	SANDS AND GRAVELS, SILTY	OPTIMUM TO +4% OF OPTIMUM	100% MAXIMUM DENSITY BY ASTM D698 METHOD A
3 AND ACCESS ROAD	GRAVELS	5% TO 8% BY DRY WGT FOR MATRIX (MAT < 3/4")	SEE CONST SPEC 5

NATIONAL PROGRAM OF INS  
SITE N  
BAKER FL  
RESERV

Figure 2



3-C

1 THE INFORMATION SHOWN ON THESE DRAWINGS IS  
2 BASED ON THE ORIGINAL CONSTRUCTION PLANS  
3 AND VISUAL OBSERVATIONS MADE DURING THE  
4 FIELD INSPECTION. DIMENSIONS OR MATERIALS  
5 INDICATED ON THESE DRAWINGS WHICH WERE  
6 BELOW GRADE OR WATER DURING THE TIME OF  
7 INSPECTION WERE NOT VERIFIED.

2. THE ELEVATIONS SHOWN ARE 1929 MSL DATUM.

REMENTS	
TEST	COMPACTION DEFINITION
+ 4% UM	100% MAXIMUM DENSITY BY ASTM D698 METHOD A
+ 4% UM	100% MAXIMUM DENSITY BY ASTM D698 METHOD A
WGT (AT 300°)	SEE CONST SPEC 5

[illegible]

**Figure 2 of 2**

APPENDIX C

PHOTOGRAPHS

FOR LOCATION OF PHOTOS, SEE FIGURE 1  
LOCATED IN APPENDIX B



PHOTO NO. 1 - General view of dam and reservoir.






PHOTO NO. 2 - Dedication and information monument.



PHOTO NO. 3 - View of upstream slope from right abutment.



PHOTO NO. 4 - View of upstream face of  
dam from left abutment.



PHOTO NO. 5 - View from right abutment of dam  
crest and roadway.



PHOTO NO. 6 - View of downstream slope of dam from right abutment.




PHOTO NO. 7 - View of downstream slope of dam from glacial erratic on left abutment.




PHOTO NO. 8 - View of riser and covered high stage inlet  
from dam.




PHOTO NO. 9 - View covered high stage inlet.



PHOTO NO. 10 - View of right  
side of riser and high  
stage trash rack.




PHOTO NO. 11 - View of left side of riser and high  
stage trash rack.



PHOTO NO. 12 - Close up view of riser structure.




PHOTO NO. 13 - View of outlet of principal spillway  
outlet pipe.




PHOTO NO. 14 - View of impact type stilling basin.



PHOTO NO. 15 - View of  
vegetation along drain-  
age of seep, juncture  
of embankment toe and  
right abutment.




PHOTO NO. 16 - Wet area in emergency spillway 100 feet downstream from axis of dam.



PHOTO NO. 17 - Seep area at approximately elevation 832 on downstream side of right abutment.






PHOTO NO. 18 - View of upstream slope near right abutment.



PHOTO NO. 19 - Surface of erosion gully at contact between the downstream slope and the left abutment. Stones have been placed in the gully at several points.



PHOTO NO. 20 - View of downstream portion of emergency spillway from axis of dam.



PHOTO NO. 21 - View of upstream portion of emergency spillway from axis of dam.



PHOTO NO. 22 - View of downstream channel and surrounding area of dam.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

For

Baker Dam Site #2

Made by

RY

Date

5/29/79

Job No

5965-11-02

Checked by

MNP

Date

6/13/79

Sheet No

1

HYDRAULICS & HYDROLOGY

Baker River Dam Site #2 Located across Berry  
Brook in Town of Warren N.H. in the  
Merrimack River Basin

Classification size - Intermediate  
hazard high

Basic Data D.A. 6.64 Square Miles  
Upstream Basin: Mountainous  
Slope 400'+ per mile

Reservoir: Recreation elev: 834.0  
Storage 500 acre-ft

Max (top of dam) elev. 870  
Storage 1848 acre-ft  
Surface area 68 acres

Dam: Earth

Length 805 ft

height 68 ft

Spillways River crest 852.0

length 24 ft

Emergency crest 861.5

width 95 feet

See Appendix "B" for Plan of Dam

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

For Baker #2

Made by

RY

Date

5/27/79

Job No

596511-02

Checked by

PMF

Date

6/13/79

Sheet No

2

Step 1 Calculation of Test Flood Inflow

Classification: Size - Intermediate  
Hazard: High

Hydrologic Evaluation Guideline Recommends

PMF for Test Flood Inflow

Use Mountainous Curve as ave stream slope is  
400+ feet/mi.

Test Flood =  $2120 \text{ acm} \times 6.64 \text{ sqmi} = 14,100 \text{ cfs.}$   
at 19" runoff.

As this is a flood control reservoir the portion of the  
storage above the recreational pool can be used to  
store a portion of the PMF

500 acre-ft at recreation pool  
1880 acre ft at crest of emergency spillway  
1380 acre ft available to store PMF

Volume of PMF  $19" / 12 \text{ in. ft} \times 640 \frac{\text{acres}}{\text{mi}^2} \times 6.64 \text{ sqmi}$   
= 6728 acre-ft

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

Made by

RY

Date

5/22/79

Job No

5965-11-02

Checked by

MUR

Date

5/13/79

Sheet No

3

For

Baker #2

Step 2 Calculation of Test Flood SurgeStage - Discharge Curve

<u>Elev</u>	<u>ft above</u> <u>Emerg. Spillway</u>	<u>A Riser Pipe</u> <u>Flow</u>	<u>B Emergency</u> <u>Spillway</u>	<u>C Crest of</u> <u>Dam</u>	<u>Total</u>
861.5 #MSL	0 ft	439 cfs	-	-	439 cfs
8630	1.5	445	280 cfs	-	725
865.0	3.5	453	1355	-	1808
867.0	5.5	460	3039	-	3499
869.0	7.5	467	5326	-	5793
871.0	9.5	475	8182	2487 cfs	11,144
871.86	10.36	478	9500	6039	16,017

A. From Baker River #2 Design Book, SCS Durham, NH  
See SCS calcs. at the end of this section

B. From Baker River #2 Design Book - Revised from 80' wide  
spillway to 95' wide as built spillway.

C. Computed as flow over Broad-crested weir

$$Q = CLH^{3/2}$$

$$C = 3.09$$

$$L = 805'$$

$$Q = 2487 H^{3/2}$$

See Figure 2 for Plot

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

Made by

RY

Date

5/31/79

Job No

5965-11-02

Checked by

WMP

Date

6/13/79

Sheet No

4

For

Baker #2

Step 3 Estimate of Surcharge Storage Effect

$$Q_P = 14,100 \text{ cfs}$$

$$\text{Runoff} = 19.0 \text{ inches}$$

$$Q_{P2} = Q_P \times \left(1 - \frac{\text{Stor}}{19}\right)$$

Stor in acre-ft read from figure 1. - 500 acre ft

$$\text{Stor in} = \frac{\text{Stor (acre ft)} \times 12 \text{ in/ft}}{6.64 \text{ sq mi.} \times 640 \text{ acre/sq mi}} = \text{Stor} (2.82 \times 10^{-3})$$

<u>Elev</u>	<u>Stor acre-ft</u>	<u>Stor (in)</u>	<u>Q<sub>P2</sub></u>
862.0	1400 acre-ft	3.95 in	11,170 cfs
865	1590	4.48	10,770
867	1720	4.85	10,500
871.5	2020	5.70	9870
869.0	1850	5.22	10,230

See Figure 2 for plot and final outflow.

From Figure 2 Outflow = 10,000 cfs


$$\text{Stage} = 870.8 \text{ ft}$$

or 0.8 above crest of dam.

Spillway Cap. at test flood 8220 cfs

At top of dam spillway 67% of TFI








Figure 2

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

For

Baker #2

Made by

RY

Date

5/27/79

Job No

5965-11-02

Checked by

MVP

Date

6/15/79

Sheet No

5

Estimate of Downstream DamageStep 1 Reservoir Storage

Top of Dam @ elev 870.0

Storage 2400 ac-ft includes  
sedimentation allowanceStep 2 Breach Outflow

$$Q_{\text{breach}} = 8/27 \sqrt{g} y_0^{3/2} w_0$$

$$w_0 = 40\% \text{ of length of dam} = (.40)(805)$$


$$y_0 = \text{height of streambed to max pool} = 68 \text{ ft}$$

$$Q_{\text{breach}} = 8/27 \sqrt{g} (.40)(805)(68)^{3/2} = 303,300 \text{ cfs}$$

$$Q_{\text{spillway}} =$$

6700

$$Q_R = 310,000 \text{ cfs}$$

Step 3 Stage - Discharge

$$Reach 1 = 3500 \text{ ft}$$

$$S_{ch} = .0111 \text{ ft/ft}$$

$$n_{ch} = .03$$

$$n_{ob} = .07$$

Stage

10 ft

15

20

25

30

32

Discharge

10,600 cfs

35,600

84,900

165,000

282,000

340,000

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

For

Baker #2

Made by

RY

Checked by

MYP

Date

5/29/79

Job No

5965-11-02

Date

6/12/79

Sheet No

6

Step 4 Reach Outflow

$S = 2400$

Reach 1A  $Q_{P_1} = 310,000 \text{ cfs}$   
 $\text{Stage}_1 = 31.0 \text{ ft}$   $\text{area} = 21,470 \text{ ft}^2$   
 $V_1 = \frac{3500 \times 21,470}{43560} = 1725 \geq \frac{2400}{2}$

Reach to long

1700' of  
3500'

$V_2 = \frac{1700 \times 21,470}{43560} = 838 \text{ acre ft}$

$Q_{P_{2T}} = 310,000 \left(1 - \frac{838}{2400}\right) = 201,800 \text{ cfs}$

$\text{Stage}_2 = 26.7 \text{ ft}$   $\text{area}_2 = 15,144 \text{ ft}^2$

$V_2 = \frac{1700 \times 15,144}{43560} = 591 \text{ acre ft}$

$V_{\text{ave}} = 714 \text{ acre ft}$

$Q_{P_2} = 310,000 \left(1 - \frac{714}{2400}\right) = 217,800 \text{ cfs} = Q_{P_1} \text{ reach 1B}$

Reach 1B  
Lower 1800'  
of 3500'

$\text{Stage}_1 = 27.4 \text{ ft}$   $\text{area}_1 = 16,100 \text{ ft}^2$

$V_1 = \frac{1800 \times 16,100}{43560} = 665 \text{ acre ft}$

$Q_{P_{2T}} = 217,800 \left(1 - \frac{665}{2400}\right) = 157,400 \text{ cfs}$

$\text{Stage}_2 = 24.5 \text{ ft}$   $\text{area}_2 = 12,337 \text{ ft}^2$

$V_2 = \frac{1800 \times 12,337}{43560} = 510 \text{ acre ft}$

$V_{\text{ave}} = 587 \text{ acre ft}$

$Q_{P_2} = 217,800 \left(1 - \frac{587}{2400}\right) = 164,500 \text{ cfs}$

Stage 25 ft

**HNTB**

HOWARD NEEDLES TAMMEN &amp; BERGENDOFF

For Baker #2

Made by

RY

Checked by

WMP

Date

5/29/79

Job No

5965-11-02

Date

6/13/79

Sheet No

7


Step 3 for Reach 2 Baker River

$$L = 13700 \text{ ft}$$

$$S_{ch} = .01159 \%$$

$$n_{ch} = .03$$

$$n_{ob} = .07$$

Stage-Discharge

$$10 \text{ ft} \quad 27,500 \text{ cfs}$$

$$15 \quad 64,600$$

$$20 \quad 127,200$$

$$25 \quad 222,500$$

$$30 \quad 356,500$$

Step 4 Reach Outflow  $Q_R = 164,500 \text{ cfs}$ 

Reach 2A

$$\text{Stage}_1 = 22.2 \text{ ft} \quad \text{area}_1 = 8851 \text{ ft}^2$$

5000' of  
13,700'

$$V_1 = \frac{5000' \times 8851}{43560} = 1016 \text{ acre ft} \leq \frac{2400}{2} \text{ Reach OK}$$

$$Q_{P_{2T}} = 164,500 \left(1 - \frac{1016}{2400}\right) = 94,900 \text{ cfs}$$

$$\text{Stage}_2 = 17.6 \text{ ft} \quad \text{area}_2 = 4960 \text{ ft}^2$$

$$V_2 = \frac{5000 \times 4960}{43560} = 569 \text{ acre ft}$$

$$V_{ave} = 793 \text{ acre ft}$$

$$Q_{P_{2c}} = 164,500 \left(1 - \frac{793}{2400}\right) = 110,100 \text{ cfs}$$

$$\text{Stage} = 18.8 \text{ ft}$$

<b>HNTB</b> HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by	RY	Date	5/29/79	Job No	5965-11-02
	Checked by	PNW	Date	6/13/79	Sheet No	8
For Baker #2						

Reach 2B  $Q_{P_1} = 110,100 \text{ cfs}$

Source 8700'  $\text{Stage}_1 = 18.8 \text{ ft}$   $\text{area}_1 = 5853 \text{ ft}^2$   
 $\text{H } 13700'$   
 $V = \frac{8700 \times 5853}{43560} = 1169 \text{ acre-ft} \approx \frac{2400}{2}$

$$Q_{P_{2T}} = 110,100 \left(1 - \frac{1169}{2400}\right) = 56,500 \text{ cfs}$$

$\text{Stage}_2 = 14.1 \text{ ft}$   $\text{area}_2 = 2850 \text{ ft}^2$

$$V_2 = \frac{8700 \times 2850}{43560} = 569 \text{ acre-ft}$$

$$V_{ave} = 869 \text{ acre-ft}$$

$$Q_{P_2} = 110,100 \left(1 - \frac{869}{2400}\right) = 70,200 \text{ cfs}$$

$$\text{Stage} = 15.6 \text{ ft}$$

### Summary

Reach	Stage
At Dam	31.0 ft
Confluence w/ Baker River	25.0 ft
At Route 25 1.6 mi d.s. of dam	18.8 ft
At Route 25 3.3 mi d.s. of dam	15.6 ft




FIGURE 3

<b>HNTB</b> HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by	<i>[Signature]</i>	Date	6/5/79	Job No	5965-11-02
	Checked by	<i>[Signature]</i>	Date	6/13/79	Sheet No	9
For <i>Baker #2</i>						

# Estimate of Surge Storage Effect with 1/2 PMF

PMF = 14,100 cfs      1/2 PMF = 7050 cfs      see pg 2

Uncontrolled Runoff with 1/2 PMF

1/2 PMF Volume      3864 acre ft      see pg 2  
Reservoir Storage      500 acre ft

for Stor(in)      see page 4

RO = 9.5 inches

$$Q_{P2} = Q_{P1} \times \left(1 - \frac{\text{Stor}}{9.5}\right)$$

see pg 4

<u>Elev</u>	<u>Stor(in)</u>	<u>Q<sub>P2</sub> 1/2 PMF</u>
862.0	3.95	4120 cfs
865.0	4.48	3720
867.0	4.85	3450
869.0	5.22	3180
871.5	5.70	2820

See Figure 2 for plot and final 1/2 PMF outflow

1/2 PMF Outflow 3450 cfs

Stage 867.0

Freeboard 3.0 ft



ITEM	UNIT	WORK PLAN	DESIGN	COMMENTS
<u>DRAINAGE AREA</u>	SQ. MI.	6.64	6.64	
<u>STORAGE CAPACITY</u>				
SEDIMENT (INC. AERATED)	AC. FT.	82	82	
BENEFICIAL	AC. FT.	478	478	
RETARDING	AC. FT.	1335	1335	
TOTAL	AC. FT.	1495	1495	
BETWEEN HIGH & LOW S.	AC. FT.	774	774	
<u>SURFACE AREA</u>				
NORMAL POOL	ACRE	35.5	35.5	
RETARDING POOL	ACRE	32	61	
DESIGN HIGH WATER	ACRE	-	37	
<u>VOLUME OF FILL</u>	CU. YD.	25,520		
<u>TOP OF DAM ELEV.</u>	FEET	872.2	861.0	
<u>MAX. HEIGHT OF DAM</u>	FEET	37	63	
<u>EMERGENCY SPILLWAY</u>				
CREST ELEVATION	FEET	863.0	861.5	
BOTTOM WIDTH	FEET	100	100	
TYPE	-	Earth	Earth	
PERCENT CHANCE OF USE	-	1	1	
AVE. CURVE NO. COND. II	-	67	67	
<u>EM. SP. HYDROGRAPH</u>				ES 1020 HYDRO
STORM RAINFALL - 6 HR.	IN.	3.75	7.72	
STORM RUNOFF	IN.	3.41	3.21	
VELOCITY OF FLOW - V	FPS	56000	56000	
PEAK DISCHARGE RATE	CFS	56000	52000	
MAX. WATER SURFACE EL.	FEET	863.0		
<u>FREEBOARD HYDROGRAPH</u>				ES 1020 HYDRO
STORM RAINFALL - 6 HR.	IN.	17.5	15.5	
STORM RUNOFF	IN.	10.52	10.89	
VELOCITY OF FLOW - V	FPS	3.2		
PEAK DISCHARGE RATE	CFS	6245		
MAX. WATER SURFACE EL.	FEET	870.0	863.0	ES 1020 HYDRO
<u>PRINCIPAL SPILLWAY</u>				ES 1020 HYDRO
RISER SIZE	FT.		2412	
MAX. LOW STAGE FLOW	CFS	76	145	ES 1020 HYDRO
ORIFICE SIZE	FT.		17-125	ES 1020 HYDRO
MAX. HIGH STAGE FLOW	CFS	420	1000	
PIPE SIZE	DIA		24	
<u>CAPACITY EQUIVALENTS</u>				
TOTAL SEDIMENT VOL.	IN.	20.5	20.5	
RETARDING STORAGE	IN.			
EM. SPILLWAY STORAGE	IN.			
TO TOP OF DAM	IN.			
<u>CLASS OF STRUCTURE</u>	-			
<u>CONSTRUCTION COSTS</u>	-			
	-			

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

## SOIL CONSERVATION SERVICE

Sh. 3 NH 677-4

✓ E.J.G. 3/12

Case 1:17-cv-00001 Document 1-1 Filed 07/26/17 Page 1 of 1

[illegible]



*Emergency*  
*Drainage*

HYDROGRAPH COMPUTATION

N 4 677

WATERSHED OR PROJECT COLEMAN CREEK STATE W. V.

STRUCTURE SITE OR SUBAREA STATE 2

DR. AREA 6.64 SQ. MI.  $T_p$  4.30 HR. RUNOFF CONDITION NO. 1

RUNOFF CURVE NO. 1 STORM DISTRIB. CURVE 1 HYDROGRAPH FAMILY NO. 2

STORM DURATION 1 HR. RAINFALL: POINT 7.20 IN. AREAL 7.24 IN.

$Q$  3.20 IN. COMPUTED  $T_p$  5.01 HR.  $T_p$  4.55 HR.

$(T_p + T_p)$  COMPUTED 1.50 USED 1.50 REVISED  $T_p$  3.01

$Q_p = \frac{484 A}{REV. T_p} = \frac{484 \times 6.64}{1.50} = 2165$  CFS.  $Q_{90} = 176$  CFS.

$Q$  (COLUMN) =  $(t/T_p)$  REV.  $T_p$ .  $Q$  (COLUMN) =  $(q_2/q_p) Q_{90}$

LINE NO.	t HOURS	Q CFS	LINE NO.	t HOURS	Q CFS	LINE NO.	t HOURS	Q CFS
1	0	0	21	1.50	176	41		
2	0.25	0	22	2.00	176	42		
3	0.50	113	23	2.50	176	43		
4	0.75	272	24	3.00	176	44		
5	1.00	475	25	3.50	176	45		
6	1.25	635	26	4.00	176	46		
7	1.50	800	27	4.50	176	47		
8	1.75	960	28	5.00	176	48		
9	2.00	1120	29	5.50	176	49		
10	2.25	1280	30	6.00	176	50		
11	2.50	1440	31	6.50	176	51		
12	2.75	1600	32	7.00	176	52		
13	3.00	1760	33	7.50	176	53		
14	3.25	1920	34	8.00	176	54		
15	3.50	2080	35	8.50	176	55		
16	3.75	2240	36	9.00	176	56		
17	4.00	2400	37	9.50	176	57		
18	4.25	2560	38	10.00	176	58		
19	4.50	2720	39	10.50	176	59		
20	4.75	2880	40	11.00	176	60		



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

4-227 H/O  
H/O  
H/O

SUB. 2 - BOS'G. EVER. WATERMASSUED - EXTENDED LAYOFF & PUNDOFF DATE

[illegible]

COMPUTATION SHEET  
SCS-522 REV 5-58

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

STATE IN PROJECT SITE 2 CHECK: ADLER, INDIAN  
BY PCW DATE 2/24 CHECKED BY SCS DATE 11/4 JOB NO. 114 577-H  
SUBJECT HIGH STAGE ORIFICE SHEET 14 OF 14

REQ'D SEDIMENT STORAGE 72 AC-FT  
" RESERVOIR STORAGE 641 AC-FT  
REQ'D FLOOD STORAGE -  
(LOW STAGE TO EMERGENCY SPILLWAY) 1335 AC-FT  
TOTAL STORAGE REQ'D 1555 AC-FT

FROM STAGE STORAGE CURVE 1555 AC-FT - ELEV. 301.5  
ELEV - CREST OF HIGH STAGE ORIFICE ELEV. 301.5  
DIFF. IN ELEV. 3.5 FT

HIGH STAGE ORIFICE (SEE SCS 50 DATED 5/1/53)  
FOR  $D = 48'$

USE  $R = 2.0' \times 12.0'$  OPENINGS  
 $A = 2 \times 2.0 \times 12.0 = 48 \text{ FT}^2$   
 $L = 2 \times 12.0 = 24 \text{ FT}$

WEIR FLOW -  $Q = 3.1 (48)^{3/2}$   
 $Q = 3.1 \times 24 \times 4^{3/2}$   
 $Q = 70.4 \text{ CFS}$

ORIFICE FLOW -  $Q = C A \sqrt{2gh}$   
 $Q = 0.67 (48.0) (8.03)^{1/2}$   
 $Q = 258.24 \text{ CFS}$

PIPE FLOW  
EMER. SPILLWAY CREST ELEV. 301.5  
PIPE OUTLET ELEV. 304.0  
DIFF. 2.5

$H = 304.0 - 301.5 = 2.5$

COMPUTATION SHEET  
SCS-522 REV 5-58

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

STATE N.H. PROJECT Site 2 - Upper Trail  
BY ANK DATE 2-10-65 CHECKED BY Y DATE 2-11-65  
SUBJECT PROPOSED PRINCIPAL SPILLWAY PIPE SHEET 2 OF 2

$$Q = C_p H^{1/2}$$

$$* C_p = \sqrt{\frac{2.9 A_p^2}{14 K_1 + K_2 (y_p + K_3 (H_p - y_p))^2}}$$

10 (refer to TR. 47)

$$C_p = \sqrt{\frac{(4.22 \times 15.57)^2}{1.0 + \frac{1.49}{1.50} - 0.412 (15.57) - 0.124 \left( \frac{15.57}{48.4} \right) (15.57)}}$$

$$C_p = \sqrt{\frac{13.17^2}{1.0 + \frac{1.49}{1.50} - 0.412 - 0.028}}$$

$$C_p = \sqrt{\frac{13.17^2}{2.547}} = \frac{2.547}{2.928}$$

$$C_p = \sqrt{\frac{2.547}{3.40112}}$$

$$C_p = \frac{55.32}{52.26}$$

$$Q = C_p H^{1/2}$$

$$Q = \frac{55.32}{52.26} (161.50 - 224.75) = \frac{55.32}{52.26} (56.75)$$

$$Q = \frac{55.32}{52.26} (7.53) = \frac{407.45}{439.1} = 0.928 \text{ CFS}$$



SITE #2 SANDY CREEK

REVISED DATA FROM 1961

Elev. 1/4-1/2	4.50- 5.00 Elev	H	H/2	Q = 53.16H	Elev 1/4-1/2	H	H/2	Q = 53.16H
553.0	504.8	48.2	24.1	1281.7	553.0	48.2	24.1	1281.7
553.2		48.4	24.2	1283.9	553.2	48.4	24.2	1283.9
553.4		48.6	24.3	1286.1	553.4	48.6	24.3	1286.1
553.6		48.8	24.4	1288.3	553.6	48.8	24.4	1288.3
553.8		49.0	24.5	1290.5	553.8	49.0	24.5	1290.5
554.0		49.2	24.6	1292.7	554.0	49.2	24.6	1292.7
554.2		49.4	24.7	1294.9	554.2	49.4	24.7	1294.9
554.4		49.6	24.8	1297.1	554.4	49.6	24.8	1297.1
554.6		49.8	24.9	1299.3	554.6	49.8	24.9	1299.3
554.8		50.0	25.0	1301.5	554.8	50.0	25.0	1301.5
555.0		50.2	25.1	1303.7	555.0	50.2	25.1	1303.7
555.2		50.4	25.2	1305.9	555.2	50.4	25.2	1305.9
555.4		50.6	25.3	1308.1	555.4	50.6	25.3	1308.1
555.6		50.8	25.4	1310.3	555.6	50.8	25.4	1310.3
555.8		51.0	25.5	1312.5	555.8	51.0	25.5	1312.5
556.0		51.2	25.6	1314.7	556.0	51.2	25.6	1314.7
556.2		51.4	25.7	1316.9	556.2	51.4	25.7	1316.9
556.4		51.6	25.8	1319.1	556.4	51.6	25.8	1319.1
556.6		51.8	25.9	1321.3	556.6	51.8	25.9	1321.3
556.8		52.0	26.0	1323.5	556.8	52.0	26.0	1323.5
557.0		52.2	26.1	1325.7	557.0	52.2	26.1	1325.7
557.2		52.4	26.2	1327.9	557.2	52.4	26.2	1327.9
557.4		52.6	26.3	1330.1	557.4	52.6	26.3	1330.1
557.6		52.8	26.4	1332.3	557.6	52.8	26.4	1332.3
557.8		53.0	26.5	1334.5	557.8	53.0	26.5	1334.5
558.0		53.2	26.6	1336.7	558.0	53.2	26.6	1336.7
558.2		53.4	26.7	1338.9	558.2	53.4	26.7	1338.9
558.4		53.6	26.8	1341.1	558.4	53.6	26.8	1341.1
558.6		53.8	26.9	1343.3	558.6	53.8	26.9	1343.3
558.8		54.0	27.0	1345.5	558.8	54.0	27.0	1345.5
559.0		54.2	27.1	1347.7	559.0	54.2	27.1	1347.7
559.2		54.4	27.2	1349.9	559.2	54.4	27.2	1349.9
559.4		54.6	27.3	1352.1	559.4	54.6	27.3	1352.1
559.6		54.8	27.4	1354.3	559.6	54.8	27.4	1354.3
559.8		55.0	27.5	1356.5	559.8	55.0	27.5	1356.5
560.0		55.2	27.6	1358.7	560.0	55.2	27.6	1358.7
560.2		55.4	27.7	1360.9	560.2	55.4	27.7	1360.9
560.4		55.6	27.8	1363.1	560.4	55.6	27.8	1363.1
560.6		55.8	27.9	1365.3	560.6	55.8	27.9	1365.3
560.8		56.0	28.0	1367.5	560.8	56.0	28.0	1367.5
561.0		56.2	28.1	1369.7	561.0	56.2	28.1	1369.7
561.2		56.4	28.2	1371.9	561.2	56.4	28.2	1371.9
561.4		56.6	28.3	1374.1	561.4	56.6	28.3	1374.1
561.6		56.8	28.4	1376.3	561.6	56.8	28.4	1376.3
561.8		57.0	28.5	1378.5	561.8	57.0	28.5	1378.5
562.0		57.2	28.6	1380.7	562.0	57.2	28.6	1380.7
562.2		57.4	28.7	1382.9	562.2	57.4	28.7	1382.9
562.4		57.6	28.8	1385.1	562.4	57.6	28.8	1385.1
562.6		57.8	28.9	1387.3	562.6	57.8	28.9	1387.3
562.8		58.0	29.0	1389.5	562.8	58.0	29.0	1389.5
563.0		58.2	29.1	1391.7	563.0	58.2	29.1	1391.7
563.2		58.4	29.2	1393.9	563.2	58.4	29.2	1393.9
563.4		58.6	29.3	1396.1	563.4	58.6	29.3	1396.1
563.6		58.8	29.4	1398.3	563.6	58.8	29.4	1398.3
563.8		59.0	29.5	1400.5	563.8	59.0	29.5	1400.5
564.0		59.2	29.6	1402.7	564.0	59.2	29.6	1402.7
564.2		59.4	29.7	1404.9	564.2	59.4	29.7	1404.9
564.4		59.6	29.8	1407.1	564.4	59.6	29.8	1407.1
564.6		59.8	29.9	1409.3	564.6	59.8	29.9	1409.3
564.8		60.0	30.0	1411.5	564.8	60.0	30.0	1411.5
565.0		60.2	30.1	1413.7	565.0	60.2	30.1	1413.7

724 H 51 3710

WFO 842913



AD-A156 376


NATIONAL PROGRAMS FOR INSPECTION OF NON-FEDERAL DAMS  
BAKER FLOODWATER RES. (U) CORPS OF ENGINEERS WALTHAM MA  
NEW ENGLAND DIV JUN 79

2/2

UNCLASSIFIED

FIG 13/15 NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

Ph. 20 ANL  
6-25-65

## SITE 2 BAKER RIVER WATERSHED

✓ 12/3/65

## EMERGENCY SPILLWAY COMPUTATIONS

$$b = 80', L = 160', n = 0.04, Z = 2.5$$

Note HNTB/ry Emer Spillway Changed to 95' width NH-677-H

[illegible]

14-675-

①                      ②                      ③

WFO 042933



DRAINAGE AREA  
BOUNDARY


BAKER RIVER DAM  
SITE 2

NATIONAL PROGRAM OF INSPECTION OF  
NON FEDERAL DAMS

BAKER RIVER DAM SITE 2  
DRAINAGE AREA

Warren, N.H.  
USGS Quad. Warren, N.H.

Scale 1:62,500  
0 FEET 0.1 MILE





APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS

# INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	COUNTY	COUNTY	CONTRACT	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE
NH	231	NED	NH 009	02	BAKER FLOODWATER RESERVOIR SITE 2	4356.4	7153.4	18JUN79

POPULAR NAME	NAME OF IMPOUNDMENT
DAVID WAYNE WILDRETH DAM	BAKER FLOODWATER RESERVOIR SITE 2

REGION BASIN	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	DIST FROM DAM (MI.)	POPULATION
01 05	BERRY BROOK	WARREN	1	539

TYPE OF DAM	YEAR COMPLETED	PURPOSES	SURFACE HEIGHT (FT.)	HYDRAULIC HEIGHT (FT.)	IMPOUNDING CAPACITIES (ACRE-FT.)	DIST OWN	FED	N	N	VER/DATE
PGHE	1969	CR	84	68	2400	500				18JUN79

REMARKS
---------

U/S	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CY)	POWER CAPACITY (KW)	NAVIGATION LOCKS
1	005 U	95	292983	6706	NO

OWNER	ENGINEERING BY	CONSTRUCTION BY
N H WATER RESOURCES RD	SOIL CONSERVATION SER	WINDHAM ROADS

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
HOWARD NEEDLES TAMMEN BERGENDOFF	17MAY79	PUBLIC LAW 92-367 8AUG1972

REMARKS
---------